April 13, 27. 2012

ADVERTISEMENT FOR BIDS
Marshall, Minnesota

TO WHOM IT MAY CONCERN:

The City of Marshall, Minnesota, will receive bids in the Council Chambers of the Municipal Building at 344 West Main Street in Marshall, Minnesota, until 10:00 a.m. on May 8, 2012, for the following projects in MARSHALL, MINNESOTA:

Project Y80: Walker Lane / Park Avenue Reconstruction Project-- This project involves the replacement of watermain and sanitary sewer utilities and street reconstruction. The proposed project will reconstruct Walker Lane and Park Avenue and described utilities.

Estimated quantities of major work items for the **Walker Lane** portion of the project are as follows:

COMMON EXCAVATION (P)	310	CY	6" CONCRETE ALLEY PAVEMENT	557	SY
AGGREGATE BASE, CLASS 5 (Mod)(CV)(P)	238	CY	8" PVC SANITARY SEWER PIPE, C-900	37	LF
CONCRETE CURB & GUTTER, DESIGN B618	100	LF	8" PVC SANITARY SEWER PIPE, SDR 35	262	LF
4" CONCRETE SIDEWALK	191	SF	6" P.V.C. WATERMAIN PIPE C-900	362	LF

Estimated quantities of major work items for the **Park Avenue** portion of the project are as follows:

COMMON EXCAVATION (P)	673	CY	6" CONCRETE DRIVEWAY PAVEMENT	183.3	SY
AGGREGATE BASE, CLASS 5 (Mod) (CV)(P)	510	CY	8" PVC SANITARY SEWER PIPE, SDR 35	365	LF
TYPE S.P. WEARING COURSE MIXTURE (SPWEC340C)	295	TON	6" P.V.C. WATERMAIN PIPE C-900	380	LF
CONCRETE CURB & GUTTER, DESIGN B618	790	LF			

Project Z02: South High Street Reconstruction Project -- This project involves the replacement of watermain, sanitary sewer and storm sewer utilities, and street reconstruction. The proposed project will reconstruct the street and described utilities on South High Street from East College Drive to East Marshall Street.

Estimated quantities of major work items for the **South High Street Reconstruction Project** are as follows:

COMMON EXCAVATION (P)	1,210	CY	4" CONCRETE SIDEWALK	7,241	SF
AGGREGATE BASE, CLASS 5 (Mod)(CV)(P)	885	CY	6" CONCRETE SIDEWALK	320	SF
TYPE S.P. WEARING COURSE MIXTURE (SPWEC340C)	527	TON	8" PVC SANITARY SEWER PIPE, SDR 35	660	LF
CONCRETE CURB & GUTTER, DESIGN B618	1,404	LF	6" P.V.C. WATERMAIN PIPE C-900	735	LF
6" CONCRETE DRIVEWAY PAVEMENT	440	SY			

Immediately following expiration of the time for receiving bids, the City Clerk/Financial Director and Director of Public Works/City Engineer or their designee will publicly open bids in the Council Chambers of the Municipal Building at 344 West Main Street.

All bidders are required to become acquainted with the extent of the work and the conditions under which the work will be performed.

All bids shall be made on the printed proposal forms of the City incorporated in the Project Manual and shall be accompanied by a cash deposit, cashier's check, bid bond or certified check, payable to the order of the City for not less than 10% of the bid.

Bids shall be directed to the City Clerk/Financial Director, securely sealed and endorsed upon the outside wrapper with a brief statement for the summary as to the work for which the bid is made.

The City Council reserves the right to reject any or all bids or any part of any bid, to waive minor defects, technicalities, or any informalities in the bidding or to advertise for new proposals, and to accept that bid deemed to be in the City's best interest.

Plans and Specifications are on file at the Office of the City Engineer located at 344 West Main Street, Marshall, MN 56258, telephone: 507-537-6773. Vendors who desire specifications may secure them from the City Engineer. Copies of the plans and specifications will be furnished on request to any prospective bidder upon a deposit of $50.00 (nonrefundable) made payable to the City of Marshall.

The bids and the responsibility of the bidders will be considered by the City Council at 5:30 P.M. on Tuesday, May 22, 2012, in the Professional Development Room at the Marshall Middle School, 401 South Saratoga Street.

No bidder may withdraw his bid for at least 90 days after the scheduled closing time for the receipt of bids.

Thomas M. Meulebroeck
City Clerk/Financial Director

Published in the *Finance & Commerce* on April 13, 2012.
Published in the *Marshall Independent* on April 13, 2012 and April 27, 2012.
Published on the City of Marshall website April 13, 2012 to May 8, 2012.
Published on the Mn/DOT eAdvert website April 13, 2012 to May 8, 2012.